# Reservoir Awareness and Responsibilities

Jillian Busch and Dave Barry
Aqualift Project Delivery Pty Ltd
2014



### Where to start...

Knowing how your distribution system works Managing the CCP's

Reservoirs are a key part of the drinking water supply

– re-contamination can occur!

Inspections conducted regularly
-The obvious and not so obvious

### **Ensuring water safety**

- Guaranteed supply
- Best quality
- And safe to drink
- Aim -> Eliminate contamination entry
  - Maintenance
  - Re-design
  - Effective renovations for long term outcomes

### **Boil water notice**



"Residents have been warned to boil drinking water after a marsupial was discovered in the local reservoir"

### Common quote...

"Our water meets all the guidelines as it leaves the treatment plant"

Aim..

"Our water is safe to drink at the customers tap"

### Inspections

The inspection process....

-not just from the ground!

- The 'usual' contamination points
- Entry hatch & platform
- Roof area
- Evidence within the tank
- Under the water line





# Vandalism – 'ROL' risk rating!









### Obvious contamination...

Faecal material from

Bird & animal

Dirt and debris

Any dust, leaf litter & 'dead' bits
 Drainage from roof & platform area
 Other materials that consume chlorine















# Not so obvious...



















# **Bucket of Water Test**





# Evidence...





### Good ideas...

Ladder assist

Sealed against contamination

Checker plate set under roof

Fall prevention

Space to work

# Entry hatch re-design



# Roof design good - no flashings, simple and effective



### Security & Access improved



### Document & take action...

### Record the evidence

- Photos
- Site check sheets




### Replace defective areas

 Entry hatches /platforms /vents /roof defects /corroded ladders & pipework

Schedule regular inspections & repairs

### **Asset Information**



### **External Condition**

4

0

#### Reservoir Details

Reservoir Hill No2

#### **General Details**

General Cleaning Safety Mixer C.P. Penetrations Valuation Comments

#### **External Inspection**

General Condition Coatings Renovations Comments

#### Internal Inspection

General Condition Coatings Renovations Comments

#### Attachments

View Images Insert Image

#### Contractors

Contractor Roles

#### Actions

Project System Project Images General Projects Maintenance Cal. Ventilation

Bird Proofing

Project Management System	Area Inspected	P Rating	Status	Comments
2	Compound	2	F	There is a compound around the external ladder, but it will not keep out determined persons - there has been dumping activity around the site so regular checks are required
<b>3</b>	Vandalism	3	F	Graffiti is an ongoing problem with this site, as it is used as a parking and dumping area
2	Walls	2	A	There is concrete spalling under three of the rafter connection areas - a more detailed structural inspection should be carried out and repairs made as necessary
<b>3</b>	Ladder External	4	D	Appears to be in good order
2	Entry Hatch	1	A	The hatch cover is sealed but the roof is draining in under the hatch frame area, where the roof sheets join the platform
2	Roof Platforms	1	А	There is an open area under the platform where it sits on top of the wall - this needs to be sealed off ASAP to stop possums from entering the tank
2	Walkways	Na	Na	No Comment
2	Roof	<b>1</b>	A	Water is ponding and draining back into the tank, where the roof joins the entry hatch frame - a gutter flashing needs to be fitted to drain the water away
<b>2</b>	Roof Hatches	Na	Na	No Comment
2	Handrails	4	D	Appears to be in good order
2	Davit	Na	Na	There is no davit fitted
		Total Control of the		11 may 12

Appears to be in good order

Possums have been entering this tank on a frequent basis - the area under the platform, where

it sits on top of the wall has been identified and needs to be sealed off ASAP

# Images & Documents

#### Reservoir Details

Reservoir Hill No2

#### **General Details**

General Cleaning Safety Mixer C.P. Penetrations Valuation Comments

#### **External Inspection**

General Condition Coatings Renovations Comments

#### Internal Inspection

General Condition Coatings Renovations Comments

#### Attachments

View Images Insert Image

#### Contractors

Contractor Roles

#### Actions

Project System Project Images General Projects Maintenance Cal

Installed Attachments
-----------------------

u <u>n</u>					
SELECT		FILENAME	COMMENT	EDIT	DELETE
	٠	4943 Disinfection site	No Comment	Edit	Delete
		4943 Entry hatch	No Comment	Edit	Delete
y	٠	4943 Inlet outlet screen	No Comment	Edit	Delete
	Q	4943 Inlet outlet screen close up	No Comment	Edit	Delete
	٠	4943 Ladder base corroded	No Comment	Edit	Delete
	0	4943 Ladder base debris	No Comment	Edit	Delete
	٠	4943 Ladder cage	No Comment	Edit	Delete
	Ō	4943 Ladder cage corroded	No Comment	Edit	Delete
	٠	4943 Ladder external	No Comment	Edit	Delete
1	O	4943 Ladder platform	No Comment	Edit	Delete

### Reports



Client Reports Asset Search **Attachments** Config Maintenance Aqualift Client Name: All State City Council User Name: jillasam49

Logout

#### Reservoir Reports

General

Analysis

Benchmarks

Critical Maint.

Maintenance

Rating Summary

Safety & Security

Structural

Exec. Summary

**Project Reports** 

Tank Inspection


#### **Project Recording**

Project Rep.

**Project Status** 

#### Overview

Overview



### **Reservoir Safety and Security Report**



26/04/2014

### **All State City Council**

Reservoir Name	Security	Contamination	Safety	Confined Space	Comment
High St No1	<b>1</b>	1	2	2	There is no secure compound around the tank The entry hatch is not secure against unauthorized access and contamination events can easily occur. Guard rails are required around the platform area. The internal ladder is heavily corroded and unsafe to use in a confined space entry or rescue situation.
High St No2	4	2	4	4	The kick plates are allowing debris and water ponding to occur
Reservoir Hill No1	4	0	2	2	The roof gutter is unsealed and full of leaf debris - the entry hatch area is also unsealed around the edges. The asbestos roof is not safe to walk on and unauthorised persons could fall through it and into the tank. There is no solid area on the roof to set up a rescue system.
Reservoir Hill No2	3	0	3	2	There is no secure compound around the tank and there has been some dumping activities around the site. There is a history of dead possums inside the tank. They are entering under the platform area, where it sits on the concrete wall. There is a cage on the ladder. A confined space rescue would be difficult to carry out.
Reservoir Hill No3	4	1	2	2	The entry hatch frame does not have a sealed front edge – natural or deliberate contamination events can occur. The internal ladder system needs to be upgraded to improve the safety of the personnel using it. A confined space entry or rescue situation would be difficult to carry out.

### Reservoir Critical Maintenance Priorities Report



#### 26/04/2014

Date: 17/06/2011 Client Name: All State City Council

WS#: 0 Reservoir Name: Reservoir Hill No2

Asset No: MA 01 Location: off Reservoir Hill Rd

Job No: 024944 Project Number: 0

Cleaning Due: 21/9/2008 Inspection Due: 17/6/2015

#### External

Area Compound	Priority 2	Status F	Comments  There is a compound around the external ladder, but it will not keep out determined persons - there has been dumping activity around the site so regular checks are required
Walls	2	Α	There is concrete spalling under three of the rafter connection areas - a more detailed structural inspection should be carried out and repairs made as necessary
Entry Hatch	1	Α	The hatch cover is sealed but the roof is draining in under the hatch frame area, where the roof sheets join the platform
Roof Platforms	1	Α	There is an open area under the platform where it sits on top of the wall - this needs to be sealed off ASAP to stop possums from entering the tank
Roof	1	Α	Water is ponding and draining back into the tank, where the roof joins the entry hatch frame - a gutter flashing needs to be fitted to drain the water away
Bird Proofing	0	Α	Possums have been entering this tank on a frequent basis - the area under the platform, where it sits on top of the wall has been identified and needs to be sealed off ASAP

#### Internal

Area	Priority	Status	Comments
Walls	2	Α	Three areas of external snalling were noted where the rafters sit on top of the

### Preventive Vs Reactive





Thankyou

